



NOTE:-

1. VALVE KEY HEAD HEIGHT TO BE BETWEEN 100 - 200MM BELOW TOP OF ACCESS LID
2. TRACER WIRE TO BE TAPED TO SIDE OF PIPEWORK RISER TO PREVENT ENTANGLEMENT WITH SPINDLE
3. CHAIN / WIRE TO SERVICE TAG TO BE OF SUFFICIENT LENGTH TO REMOVE FROM PIT FOR READING
4. STAINLESS STEEL EYE BOLT TO BE AS HIGH AS POSSIBLE FOR CONNECTION OF TRACE EQUIPMENT
5. ALL TRACE WIRE TO BE TESTED AT TIME OF CONSTRUCTION

TITLE

SLUICE VALVE RISER DETAIL WITH TRACE WIRE

PROJECT:

STANDARD DETAILS
HYDRAULIC SERVICES



PLANNING, DESIGN & CONSTRUCTION
CORPORATE SERVICES

170 KESSELS ROAD, NATHAN, BRISBANE, QLD. 4111 PH:(07) 3735 7111 griffith.edu.au

DATE

11/08/2021

DRAWN BY

JS

SCALE

NOT TO SCALE

APPROVED BY

JA

DISCIPLINE

HYDRAULIC

REVISION

2

PROJECT No:

N/A

DRAWING No:

GSD-803

SHEET No:

1 of 1