

8.00 External Walls

8.01 Generally

The colour, materials and texture of external walls shall reflect the proposed use and functionality of the project and shall be selected on a life-cycle cost basis taking into account the long term maintenance and operation of the wall and its finishes over twenty (20) years, as well as the initial cost of construction. Innovative design solutions are encouraged within these parameters.

The materials and texture of external walls shall be approved by GU at the preliminary sketch design stage.

It is a Mandatory requirement that all walls shall be waterproof.

8.02 Construction

External walls to buildings shall be designed with particular care and consideration given to the possible future effects of shrinkage, cracking and thermal movement.

Mortar joints to face brick and face blockwork shall be ironed to a half round radius.

Façade staining shall be avoided by careful design and detailing to shed water clear of the building, clear of lower projections and clear of pathways. Parapet cappings and window framing shall be designed to ensure facade staining is avoided.

8.03 In-situ Finishes

If exposed concrete is proposed and approved by CLF, it shall have a minimum Class 2 'off-form' finish.

Where the concrete finish and colour control does not meet the satisfaction of the Superintendent, such surfaces shall be rendered or receive another acceptable applied finish.

Any exposed concrete edges shall be treated to ensure compatibility with the predominant finish to the external wall surfaces.

Standard grey concrete masonry is not acceptable as a permanent external finish, however coloured concrete masonry may be used subject to the approval of the Deputy Director (PD&C) CLF. Split-face masonry blocks *shall not* be used.

8.04 Applied Finishes

Applied finish shall be a full system such as that manufactured by 'Rockcote' or 'Granosite Coating Systems', and shall have a minimum ten (10) year unconditional guarantee.

Applied finish on concrete masonry shall be applied over a 4mm minimum thick 'Rockcote PM100' or 'Granoplast' Fine/Medium render coat.

Application of applied finishes shall conform to the manufacturers printed instructions by approved applicators, to ensure validity of the guarantee from the manufacturer.

Spray applied finishes to external surfaces is not permitted.

8.05 Colours

Colours for use on the building are to be submitted to CLF for review and comment prior to the preparation of a colour board to be presented to the Project User Committee for formal approval.



8.06 Sun Shading & Screening

Sunshading and screening shall be provided as required by the project to minimise the life cycle costs of air conditioning and to eliminate the need for curtains and blinds as sun control measures.

Consultants are to produce Solar Charts illustrating shadow angles resulting from proposed sun control devices to be used on the project at Schematic Design stage.

The effectiveness of the proposed devices shall be further tested during design development by producing floor plans which indicate the sunlight penetration into the building. These floor plans shall incorporate the indicative furniture layouts.

8.07 Provision for Building Signage

Provision shall be made in the design of the facade around the main entry to the building for the installation of the building name and number.

Building identification signage shall be in accordance with the requirements of the GU Signage Manual.

8.08 Sealants

Sealants shall be selected to be appropriate for their application and shall be colour matched to the finished surface. Only sealants with no VOC emissions or levels of VOCs below 420g/L are to be used.

8.09 External Protection

Provide approved bollard protection to all external areas of buildings liable to vehicle damage.